

# The first Low Temperature Centralized Heat Supply System in Latvia: the pilot of Belava Parish - Gulbene

Dr.sc.ing. Vladimirs Kirsanovs, Riga Technical University

Dr.sc.ing. Ieva Pakere, Riga Technical University

Professor, Dagnija Blumberga, Riga Technical University

Professor, Francesco Romagnoli, Riga Technical University







- The former District heating (DH) system at Belava consisted of a wood boiler house and 9 buildings
- DH includes different groups of consumers: public buildings (i.e. local authority, kindergarten, mail), 1 cultural centre, 1 recreation building, 1 shop, 1 multifamily residential building and 4 private houses
- Public building, cultural house and shop are renovated
- Multifamily residential building is not insulated and have high heat consumption around 190 kWh/m, per year
- Existing boiler house: 1 MW fire wood boiler.






## Main problem


### Existing DH system was old and not effective

#### Heat transportation

- disproportionate DH grid
- old pipes with bad quality insulation
- heat loss in the grid ~40 %.











## Main problem (II)

#### Heat production

- low boiler efficiency (50 60 %)
- 3 workers for wood log preparing and manual loading into boiler

#### Heat consumers

no heat meter for each consumer





- DH grid and building heating system are not separated with heat exchanger
- payment based on EUR/m² and not depending on consumers heat consumption
- consumers are not motivated to save heat energy
- high heat supply tariff 87.50 EUR/MWh





## Aim and scope of the pilot measure

The implementation of a modern DH and smart metering system within existing buildings:

- Transformation of existing DH to LTDH to develop demonstrative pilot example
- **Provide LTDH** for two insulated buildings to three different consumer groups in Belava Parish: culture center, local government and kindergarten
- Develop a smart metering system for LTDH monitoring as base for a future integrated energy management system
- Testing of LTDH implementation strategy, weak point recognition and suggestion determination for strategies improvement
- Change of reluctant attitude towards LTDH implementation by presentation of achieved benefits
- Reduce CO2-emissions from DH system





## Pilot measure timeline

Existing DH system
analysis
LTDH implementation
strategy development


2017/18

Implementation of measures

2018/19

Conclusions and recommendations for LTDH implementation at other parishes

2019/20



DH grid reconstruction and heat supply transformation

DH system optimization






## Description of the implemented technology

• **Heat production** – actual heat load calculation and installation of the container type house with automatically operated 200 kW pellet boiler selection with high heat production efficiency











# Description of the implemented technology (II)


#### Heat transportation –

• DH grid length decrease (disconnection of 4 private houses and boiler house placement closer to main heat consumers)

replace of old pipes to new industrially isolated pipelines

decrease the temperature in grid - 65°/35° for renovated buildings and 80°/60° not insulated buildings (two separate circulation loops)









## Description of the implemented technology (III)

#### Heat consumers

- substations and heat distribution system for each consumer
- heat meter installation for consumers and ensure payment based on a heat meter readings








## System monitoring

- LTDH system monitoring was organized by installation of smart metering system installation for:
  - Produced heat monitoring
  - Heat consumption monitoring
  - Indoor climate monitoring for each building
  - Outdoor temperature and solar radiation monitoring



- heat consumer monitoring




monitoring

- outdoor temperature



# System optimization

- Low correlation between outside temperature and supply temperature from boiler house was identified
- The adjustment of the boiler house automation to increase the higher DH system efficiency









	2017/18	2018/19	2019/20	
Boiler house efficiency [%]	~ 55	83,7	90,3	
Heat loss at DH grid [%]	~40	4,6	3,8	
Fuel consumption [MWh/year]	1 179	470	459	
Electricity consumption, [kWh/MWh]	~20-25	10,9	10,1	
Heat supply tariff [€/MWh]	87,50	69,07	69,07	

• Cost savings per year average: 16 900 €

• Investment payback period: 11 years







#### House owners, apartment owners and apartment building managers:

- Reduced heating costs
- Improved indoor climate conditions

#### • Heat suppliers:

- Improved heat production efficiency
- Reduce heat transfer losses
- Possible integration of waste heat sources

#### Municipality:

- Improved DH energy management from installation of stationary and mobile smart metering systems
- Knowledge about 4<sup>th</sup> generation DH and implementation in new projects

#### Other municipalities:

Good practice example and action plan for LTDH implementation





## Conclusions

- The pilot project implementation offers the opportunity to identify main barriers and bottlenecks for a successful realization at a larger scale.
- An in-depth analysis of the existing situation and developing a clear and tailored action is necessary for new LTDH system construction or existing DH transformation to low temperature.
- System monitoring and optimization are necessary to preclude the possibility of shortcomings.
- Pilot activities supplement the development of pilot energy strategies in municipalities and regions.
- Existence of a reluctant attitude toward LTDH implementation does to the lack of knowledge.
- In-formative campaigns are necessary to change people attitude and show a positive experience of LTDH project realization.







Dr.sc.ing. Vladimirs Kirsanovs, <u>vladimirs.kirsanovs@rtu.lv</u>

Institute of Energy Systems and Environment

Riga Technical University



